





Necessary preparations before installing a 3 or 4-group Rocket coffee machine in Switzerland

Attention:

- Please do *not* plan the installation simultaneously with the plumber, electrician or carpenter: we only hook up to finished connections ready to plug in.
- Avoid installations during the construction phase to protect the machine.
- Tick all the boxes with the construction supervisor and inform us 48h before the installation if anything is not ready!
- Water must be running and all sockets powered!
- In case of unexpected delays, we will have to charge additional costs.

Installation-compartment	Height = full counter height (800mm)	Directly underneath the machine for sockets ①, water in- ② and outlet ③, and water-filter	<input checked="" type="checkbox"/>
	Width = min. 400mm		<input type="checkbox"/>
	Depth = full counter depth (600mm)		<input type="checkbox"/>
Hole in tabletop directly to the installation compartment (for water pipes and cables)		Diameter \varnothing 80 mm	<input type="checkbox"/>
		Centered underneath the machine	<input type="checkbox"/>
① Sockets	1x type 25 socket for coffee machine (3 x 400V/16A,3P,N +E)		<input type="checkbox"/>
	1 plug-in slot type 13 socket per grinder		<input type="checkbox"/>
② Water inlet	1x 3/8" fresh water line with stopcock. Cold fresh water with at least 3 bar line pressure		<input type="checkbox"/>
③ Water outlet	1x open syphon with at least 40 mm diameter and 150 mm riser		<input type="checkbox"/>

Visualization

